



**CONFIDENTIAL**

CREATED BY: HOOSIER CRANE SERVICE

**GORBEL**

600 FISHERS RUN  
P.O. BOX 593  
FISHERS, NY 14453-0593

WSJ360-NP6-500-8-14

CAPACITY: 500 LBS

SPAN: 14 FT

H.U.B.: 8 FT

QUANTITY: 1

SHIPPING WT.: 801 LBS

DRAWN:

DATE: 4/29/2020

TROLLEY TRAVEL: 11'-11/16"

**FOUNDATIONLESS REQUIREMENTS:**

- CENTERED ON A SQUARE FOOT AREA THAT IS FREE FROM CRACKS, SEAMS, AND WALLS.
- REINFORCED CONCRETE WITH PRESSURE OF 3000 PSI AND SOIL PRESSURE OF 2500 PSF.
- CHEMICAL ANCHOR BOLTS TO WITHSTAND A MINIMUM OF 2,850 LBS. OF PULL OUT FORCE.
- CONCRETE MUST CONTAIN A MINIMUM OF WIRE MESH REINFORCEMENT.
- IT IS THE RESPONSIBILITY OF THE DEALER AND END USER TO VALIDATE THE MOUNTING STRUCTURE IS SUFFICIENT TO RESIST CRANE LOADINGS. GORBEL ASSUMES NO LIABILITY FOR FAILURES OF EQUIPMENT OR STRUCTURES NOT SUPPLIED BY GORBEL.

DO NOT SCALE FROM THIS DRAWING.

**500 LB CAPACITY**